

Figure 5.1 Unit Price Schedule

ITEM	UNIT	UNIT PRICE	COMMENTS
Trail Surfacing			
1. Rough Grading	LM	\$2.50	includes leveling and packing after leveling
2. Construct new stonedust limestone screening trail	LM	\$30.00	
3. Construct new asphalt trail	LM	\$70.00	
4. Upgrading gravel tar and chip	LM	\$12.00	includes 1 coat primer and 2 coats surface (areas requiring "trail hardening")
5. Upgrading gravel trail to Asphalt	LM	\$45.00	price includes some upgrades to the base
6. Construct single track trail	LM	\$10.00	includes clearing and grubbing with minor regrading to eliminate high and low points
	LM	\$0.00	
Signage			
1. Type A Sign: Motorist/Gateway	each	\$13,000.00	based on cost of previously constructed units
2. Type B Sign: Major Trailhead Kiosk	each	\$3,000.00	
3. Signboards for Type B sign	each	\$2,000.00	does not include graphic design
4. Type C Sign: Trail Directional Sign	each	\$200.00	includes markers and post
5. Type D Sign: Trail Marker Sign	each	\$100.00	includes markers and post
6. Type E Sign: Interpretive Sign	each	\$800.00	
7. Signboards for Type E Sign	each	\$800.00	does not include graphic design
8. Traffic Signs - On-road	each	\$200.00	per MTO specs
9. Regulatory Signs (on trail)	each	\$75.00	same as 1 above
Barriers and Access			
1. Lockable Gate (2 per road crossing)	each	\$2,000.00	price indicated for one side of road (2 required per road crossing)
2. Berming/boulders at road crossing	each	\$500.00	price indicated for one side of road (2 required per road crossing)
3. Page Wire Fencing	LM	\$12.00	grca reports as low as \$10.00/lm
4. Parking Lot at staging area (15 car capacity-gravel)	each	\$10,000.00	
5. Chain Link Fencing	LM	\$50.00	range of \$35.00-\$65.00/lm depending on height, gauge and site conditions
6. Signalized Road Crossing	each	\$50,000.00	intersection pedestrian signal (IPS)

Structures

1. Cuvert repair (major)	each	\$2,500.00	
2. Culvert Repair (minor)	each	\$500.00	
3. New Concrete Box Culvert (walkthrough)	each	\$10,000.00	assumes length of 10m+/- with good access for construction
4. 450mm dia. csp culvert	each	\$1,500.00	assumes length of 10m+/- with good access for construction
5. New boardwalk (pedestrian-light duty)	LM	\$600.00	new construction-includes footings and decking 2.5m wide

Site Furnishings

1. Benches	each	\$600.00	can be as low as \$250.00 for "low tech" bench
2. Garbage Container	each	\$150.00	
3. Bicycle Rack	each	\$750.00	holds 6 bicycles
4. Servicing of Port o Let	each	\$600.00	per season
5. Construct washroom building	each	\$3,500.00	wood structure with concrete holding tank

On Road

1. Pave Shoulders	LM	\$140.00	price for two sides
2. Construct new shoulder and pave	LM	\$220.00	price for two sides
3. Pave shoulder as part of road reconstruction	LM	\$180.00	price for two sides
4. Construct Bike Lane-new Construction	LM	\$360.00	price for two sides
5. Construct bike lane as part of reconstruction	LM	\$180.00	price for two sides
6. Paint bike lane on existing road	LM	\$9.00	price for two sides
7. Construct wide shared lane -new construction	LM	\$360.00	price for two sides
8. Construct wide shared lane as part of reconstruction	LM	\$180.00	price for two sides
9. On-road signed route	LM	\$2.00	price for two sides
10. Replace catch basin covers with bicycle friendly model	each	\$260.00	
11. Traffic Control sign	each	\$200.00	
12. Construct Concrete sidewalk	LM	\$75.00	one side of street only
13. Route Sign	each	\$100.00	